


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Stafford County. Sec. 24 Twp. 24 Rge. 14 (E) (W)  
Location as "NE/CNWSW" or footage from lines SW SW SW  
Lease Owner Addis Oil Operations  
Lease Name Koelsch #1 Well No.  
Office Address Wichita, Kansas 67208  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 9/19/73 19  
Plugging completed 10/3/73 19  
Reason for abandonment of well or producing formation depleted.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein  
Producing formation Depth to top Bottom Total Depth of Well 4290 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	249	none
				5 1/2	4032	1370

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, ran sand to 3700' and dumped 5 sacks cement. Loaded hole, shot pipe at 3099', 2975', 2885', pipe parted down hole, pulled 34 joints of 5 1/2" casing. Allied pumped 3 sacks hulls, 15 sacks gel and 125 sacks cement.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 9 1973  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of October, 1973

My commission expires



Margaret Melcher  
Notary Public.

D R I L L E R ' S   L O G

COMPANY: WHITE EAGLE OIL COMPANY      LOCATION: SW 87 SE 24-24S-11W  
 CONTRACTOR: HILTON DRILLING COMPANY, INC.      Stafford County, Kansas  
 FARM NAME: KOEHLISCH NO. 1      ELEVATION: 1947 LF  
 COMMENCED: 9-11-52  
 COMPLETED: 10-1-52  
 Casing used: 8 5/8 set at 249 ft. w/250 sacks  
 5 1/2 set at 4032 ft. w/150 sacks

Sand and gravel	100
Sand and shale streaks	160
Blue Shale and shells	210
Hard Sand	230
Gray shale and Red Bed	250
Red Bed	840
Anhydrite	865
Shale and shells	1615
Lime and shale	1720
Lime broken	1815
Lime	2295
Lime and shale	2965
Lime	3061
Lime and shale	3163
Lime	3467
Lime and shale	3591
Lime	3892
Lime and shale	3930
Lime and conglomerate	3873
Conglomerate (cherty)	4030
Conglomerate, chert and shale	4049
Conglomerate (cherty)	4076
Viola lime and chert	4093
Viola chert	4165
Simpson	4195
Simpson, shale, sand, and lime	4229
Lime	4263
Arbuckle	4290
Total Depth	4290

RECEIVED  
 STATE CORPORATION COMMISSION

SEP 19 1973

CONSERVATION DIVISION  
 (Wichita, Kansas)

STATE OF KANSAS )  
 ) SS  
 COUNTY OF MARTON )

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

HILTON DRILLING COMPANY, INC.

by Henry Peacock  
 Henry Peacock, Secretary

Subscribed and sworn to before me this  
 3rd day of October, 1952.

Margaret Whitmore  
 Notary Public

My commission expires April 4, 1956.