

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Stafford County, Sec. 24 Twp. 24 Rge. 14 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NW SW
Lease Owner Addis Oil Operations
Lease Name Koelsch #5 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 1/11/73 19
Plugging completed 1/18/73 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation Depth to top Bottom Total Depth of Well 3895 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	831	none
				5 1/2"	3894	2757'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, ran sand to 3650' and dumped 5 sacks of cement.
Shot pipe at 2897', 2800', pulled 82 joints. Set 10' rock bridge
at 360' and dumped 10 sacks of cement with 5" bailer. Set over
night plug. Bailed hole dry, dumped 6 yards ready mix to plug well.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
FEB 9 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

KNIGHT CASING PULLING CO., INC.

Name of Plugging Contractor CHASE, KANSAS
Address

STATE OF KANSAS COUNTY OF RICE, ss.

NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

CHASE KANSAS

(Address)

SUBSCRIBED AND Sworn to before me this 19th day of January, 1973



MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

My commission expires

Notary Public.

DRILLER'S LOG

COMPANY: WHITE EAGLE OIL COMPANY
 CONTRACTOR: HILTON DRILLING COMPANY, INC.
 FARM NAME: KOELSCH NO. 5
 COMMENCED: 6-18-53
 COMPLETED: 6-30-53

LOCATION: SW NW SW
 Sec. 24-24-24
 Stafford County,
 Kansas

Casing Used: 8-5/8 set at 831' w/500 sacks 5 cc
 5-1/2 set at 3894' w/125 sacks

Clay Sand	40
Sand and Gravel	105
Shale and Shells	220
Red Bed Shale	580
Red Bed Shale and Shells	823
Anhydrite	855
Red Bed Shale, Shells	1235
Shale and Shells	1600
Lime and Shale	1700
Broken Lime	1895
Lime	2030
Sand and Lime	2160
Lime	2485
Lime and Shale	3075
Broken Lime	3124
Lime Shale	3226
Lime	3446
Lime and Shale	3584
Lime	3860
Lime and Shale	3895
Total Depth	3895

TOPS:

Heebner	3449
Brown Lime	3584
Kansas City	3613

RECEIVED
 STATE CORPORATION COMMISSION

NOV 21 1972

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

HILTON DRILLING COMPANY, INC.

Henry Peacock
 Henry Peacock, Secretary

Subscribed and sworn to before me this 2nd day of July, 1953.

My commission expires 4-4-56.

Margaret Whitmore
 Notary Public