

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 15 Twp. 24S Rge. 11W (EXX) (W)

Location as "NE/CNW/SW" or footage from lines NE NW NE

Lease Owner Braden - Zenith, Inc.

Lease Name Z - U #10 Well No.

Office Address 200 East First Street, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 6, 1971 19

Application for plugging filed December 6, 1971 19

Application for plugging approved December 6, 1971 19


Plugging commenced 3:30 PM, December 6, 1971 19

Plugging completed 5:15 PM, December 6, 1971 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Russell Biberstein

Producing formation Depth to top Bottom Total Depth of Well 3830 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	257'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 257'.
Set Howco plug, 1/2 sack Hulls, 20 sacks cement.
Filled hole to 40'. Set Howco plug, 1/2 sack
hulls, 15 sacks cement. 2 sacks in rathole.

RECEIVED
STATE CORPORATION COMMISSION
DEC 16 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor STERLING DRILLING COMPANY

Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS, COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of December, 1971

Bernard Lauder milk, Notary Public.

My commission expires

BERNARD LAUDERMILK - NOTARY PUBLIC
My Commission Expires Jan. 22, 1974

15-185-20393-0000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- Z - U #10
Located: NE NW NE, Section 15-248-11W, Stafford County,
Kansas

OWNER: Braden - Zenith, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 27, 1971
COMPLETED: December 6, 1971

TOTAL DEPTH: 3830'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 95 Sand	Ran 13 joints 10 3/4" O.D. surface casing, 246' cemented at 257' K.B. with 285 sacks 50/50 Pozmix with 3% HA5, 2% gel. Plug down 1:15 AM,
95 - 262 Clay and Shale	
262 - 745 Shale and Shells	
745 - 1120 Shale	
1120 - 2810 Lime and Shale	
2810 - 2820 Lime	
2820 - 3025 Shale and Lime	
3025 - 3750 Lime	
3750 - 3780 Lime, Shale, Sand, Chert	
3780 - 3817 Lime and Shale	
3817 - 3830 Lime	Plugged.

RECEIVED
STATE CORPORATION COMMISSION
DEC 16 1971
CONSERVATION DIVISION
Wichita, Kansas