


Give Attention Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Stafford County. Sec. 15 Twp. 24S Rge. 11W (E) (W)
Location as "NE/CNW/SW" or footage from lines CW/2 NE/4 NE/4
Lease Owner E. H. Riggs
Lease Name Equitable Life Well No. 2
Office Address 408 Rule Building - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed March 24 1955
Application for plugging approved March 25 1955
Plugging commenced April 6 1955
Plugging completed April 12 1955
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3825 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	225'	None
				5-1/2"	3791'	2892'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from 3825' to 3760' and ran 5 sacks of cement. Mudded hole by pumping in 15 sacks of mud through oil string. Bailed hole to 225', set a 15' rock bridge and ran 20 sacks of cement. Mudded hole to 40', set a 10' rock bridge and ran 10 sacks of cement. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
E. H. Riggs (signature of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. H. Riggs
408 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of May, 1955

My commission expires March 3, 1958

Eva L. Murray
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

MAY 10 1955

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 15 24 R 11W
BOOK 106 LINE 44

LOG OF WELL

SHEET No. _____

District **Kansas** Owner **Alf Landon, taken over by The Texas Company Farm Habitable Life** Well No. **2**

FORMATION	DEPTH	AMOUNT	COLOR	HARD OR SOFT	DEPTH CORES TAKEN	REMARKS
Surface soil, sand & gravel	180	100				
Grey & red shale	225	45				
Red beds	570	45				
Anhydrite	600	30				
Green & Red shale	670	270				
Blue grey shale	1200	330				
Shale & salt	1530	330				
Anhydrites & shale	1750	280				
Limestone	1925	175				
Limestone & shale	2340	315				
Shale & lime shells	2600	540				
Sandy shale	2920	40				
Topeka	3230	310				
Shale	3366	446				
Dense brown lime	3571	5				
Shale	3390	25				
Lansing limestone	3420	24				
Shale	3440	20				
Limestone	3465	25				
Shale	3475	10				
White Limestone	3525	50				
White Porous	3532	7				
Dense Limestone	3570	38				
White Porous	3500	10				
Limestone	3565	85				
Shale	3575	10				
Buff dense limestone	3680	13				
Red shale	3708	20				
Green & red Kinderhook shale	3756	48				
Misner cherty limestone	3765	9				
Oil Saturated, weathered chert & Petroleum residue	3770	5				
Green Shale	3790	20				
Viola dolomite	3801	11				
Crystalline Limestone	3818	17				
Cherty dolomitic limestone	3825	7				
TOTAL DEPTH	3825					

STAMPED
 THE TEXAS COMPANY
 KANSAS

PLUGGING
 FILE NO. 15-185-10359-110
 BOOK PAGE 106 LINE 44