

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
***Make Required Affidavit**
Mail or Deliver Report to:
Conservation Division
State Conservation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

**Strike out upper line
when reporting plug-
ging off formations.**

NORTH

**Locate well correctly on above
Section Plat**

Stafford County. Sec. 3 Twp. 24S Rge. (E) 11 (W)
Location as "NE¼NW¼SW¼" or footage from lines C-E/2-SW-SW
Lease Owner. Deep Rock Oil Corp.
Lease Name. James S. Henry Well No. 3
Office Address. Box 1051 Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed. 11/15/41 19
Application for plugging filed. 11/21/47 19
Application for plugging approved. 11/24/47 19
Plugging commenced. 3/26/48 19
Plugging completed. 3/31/48 19
Reason for abandonment of well or producing formation. well went dry

If a producing well is abandoned, date of last production.....Dec. 1947
Was permission obtained from the Conservation Division or its agents before plugging was commenced?.....yes

Name of Conservation Agent who supervised plugging of this well.....Charlie Stough.....

Producing formation.....viola lime..... Depth to top.....3749'..... Bottom..... Total Depth of Well.....3770'..... Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Filled hole with mud & rock to 3750'--ran 6 sks. cement--filled to 3720'. Filled with mud to 275'--set rock bridge & ran 20 sks. cement at 275'. Filled with mud to within 15' of top. Dumped 10 sks. cement to fill hole to top & bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....Deep Rock Oil Corp.
Address.....Box 429.....Hutchinson, Kans.

STATE OF _____, COUNTY OF Keno, ss.

..... (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Lukhmi

Box 429 Hutchinson Kans.
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of April, 1948

My commission expires _____

11-26-51



8-45-6M

4-2-48

Log on James S. Henry #3

Sec. 3 Twp. 24 Rge. 11W

Stafford County, Kansas

0	100	Shale and sand
100	175	Red rock and shale
175	540	Shale
540	565	Anhydrite
565	1540	Shale
1540	1728	Lime
1728	1865	Lime and Shale
1865	1920	Lime
1920	1960	Shale
1960	2250	Shale and Lime
2250	2270	Shale
2270	2300	Lime
2300	2340	Shale and Lime
2340	2425	Shale
2425	2450	Lime
2450	2639	Shale
2639	2700	Shale and Lime
2700	2745	Shale
2745	2785	Lime and shale
2785	2810	Lime
2810	2860	Shale
2860	2890	Lime
2890	2980	Lime and Shale
2980	3060	Lime
3060	3140	Lime and Shale
3140	3200	Lime
3200	3375	Shale
3375	3455	Shale and Lime
3455	3665	Lime
3665	3735	Shale
3735	3751	Cored - top Viola Lime 3749'
3751	3770	Viola Lime
3770		Total Depth

Pipe record:

548' of 10 3/4" 35# LW S.H. csg.--cemented w/ 355 sks. cement
 3750' of 7" csg.

589' of 20# LW S.H. on bottom

3161' 24# new Smls. on top

--cemented w/ 200 sks. cement

