

9

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-079-19039-0000

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Smith of H.C. Bennett has this

date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: H.C. Bennett

Complete Address: 1212 Union Natl. Bldg. Wichita, Kansas

Lease Name: Hurty Well No. # 1

Location: SW NW NW Sec. 18 Twp. 23 Rge. 3W (E) (W)

County Harvey Total Depth 3381' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Smith was instructed to plug the well as follows:

- 8 5/8"-496'-Circulated w/cement. 5 1/2"-3315'-Cemented. Sand hole to 3310'.
- 5 Sax.cement 3310' to 3260'. Mud 3260' to 200'. Bridge 200' to 190'.
- 25 Sax.cement 190' to 115'. Mud 115' to 40'. Bridge 40' to 30'.
- 10 Sax.cement 30' to 0. Pulled 2300'-5 1/2"-pipe.

Very truly yours,

Hugh Scott
Conservation Division Agent