

State of Kansas



JOHN ANDERSON, Jr. Governor
 WILLIAM L. MITCHELL, Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAY 25 1965

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Duke Burt of Burt Drilling Company has this date requested permission to plug the following described well:

Mr. Burt guarantees payment of the plugging fee.

Operator's full Name: Icer Addis

Complete Address: Box 519, Great Bend, Kansas

Lease Name: Neill Well No. # 1

Location: SE NW NE Sec. 27 Twp. 24 Rge. 14 (E) (W) W

County Stafford Total Depth 4230' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burt was instructed to plug the well as follows:

210' of 8 5/8" surface pipe, cement circulated. Fill hole with drilling mud to 195', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to the base of the cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent