

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 5 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Radke of Garvey Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Radke guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 300 W. Douglas Wichita, Ks

Lease Name: Suiter E Well No. 1

Location: SW/NE/SE Sec. 21 Twp. 24 Rge. 14 (E)(W) W

County: Stafford Total Depth 3731 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Radke was instructed to plug the well as follows:

286 ft of 8 5/8 surface pipe cemented with 250 sacks. Plug  
at 600 ft with 40 sacks cement. 2nd plug at 275 ft with  
30 sacks cement. Mud to 40 ft, plug, 1/2 sack hulls, 10  
sacks cement to surface. 2 sacks cement in rat hole.

2 sacks cement in mouse hole. Globe Cementing Co. Great  
Bend, Ks

Very truly yours,

L. Russell Bickerton  
Conservation Division Agent