

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 28 TWP. 24 RGE. 14 E/W
Location as in quarters or footage from lines:
NW NE NW

Lease Owner Roxana Corp.
Lease Name SNYDER Well No. #1
Office Address P.O. Box 1162 Great Bend, KS 67530
Character of Well (Completed as Oil, Gas or Dry Hole):
Date Well Completed 5-11-82
Application for plugging filed 5-11-82
Plugging commenced 5-11-82
Plugging completed 5-12-82
Reason for abandonment of well or producing formation

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz
Producing formation _____ Depth to top _____ bottom _____ T.D. 4324
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Bottom Plug: @ 700' w/60 sacks cement thru drill pipe
Middle Plug: @ 300' w/40 " " " " "
Top Plug: @ 40' w/solid bridged plug 10 sacks cement
10 sacks cement in Rat Hole 5-17-82

RECEIVED
STATE CORPORATION COMMISSION

MAY 17 1982

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Lobo Drilling Co.

STATE OF Kansas COUNTY OF Barton, ss.
Ervin Neighbors (employee of owner) or ~~owner or operator~~ of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Ervin Neighbors
Box 877 Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 14 day of May, 1982

Dorothy M. Nague
Notary Public.

My Commission expires: 4-29-86

DRILLERS WELL LOG

DATE COMMENCED: May 5, 1982
 DATE COMPLETED: May 12, 1982

Roxana Corporation
 SNYDER #1
 NW NE NW
 Sec. 28, T24S, R14S
 Stafford County, Ks.

ELEVATION: 1977 K.B.

0 - 914' Surface Soil, Clay, Shale
 914 - 935' Anhydrite
 935 - 3539' Shale, Lime
 3539 - 3543' Shale
 3543 - 3559' Lime & Shale
 3559 - 3575' Lime
 3575 - 3676' Shale & Lime
 3676 - 3705' Lime & Shale
 3705 - 4235' Lime, Shale, Chert
 4235 - 4316' Shale, Sand
 4316 - 4324' Dolomite
 4324' RTD

FORMATION DATA

Anhydrite	914'
Heebner	3539'
Toronto	3559'
Douglas	3575'
Br. Lime	3676'
Lansing	3705'
Mississippi	4084'
Viola	4161'
Simpson	4235'
Simpson Sand	4272'
Arbuckle	4316'
RTD	4324'

Surface Pipe: Set new 8-5/8",
 23# pipe at 426' w/325 sacks
 60/40 pozmix, 2% gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 12 day of May 1982.

My Comm. Expires:

4-29-86

Maureen McHague
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 17 1982
 CONSERVATION DIVISION
 Wichita, Kansas