


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

Stafford County. Sec. 21 Twp. 24S Rge. 14 (E) 14 (W)
Location as "NE/CNW/SW" or footage from lines C SW SE SE
Lease Owner SUNRAY MIDCONTINENT OIL COMPANY
Lease Name Spiter 'A' Well No. 1
Office Address P. O. Box 788, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-7 19 57
Application for plugging filed 1-7 19 57
Application for plugging approved 1-8 19 57
Plugging commenced 1-7 19 57
Plugging completed 1-7 19 57
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4287 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	307'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with drilling mud, 1/2 sack hulls; set wooden plug and ran 55 sacks cement at 300'; filled hole with drilling mud, 1/2 sack hulls; set wooden plug and ran 15 sacks cement to surface. Plugging completed.

Well log attached.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor HALLIBURTON OIL WELL CEMENTING
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Norman E. Montgomery (employee of owner) or ~~XXXXXXXXXX~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Norman E. Montgomery
P. O. Box 788, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of January, 19 57

My commission expires December 21, 1960

[Signature]
RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1957
1-18-57
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 21 T 24 R 14W
BOOK PAGE 132 LI E 1

Sunray Mid-Continent Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
January 14, 1957

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: December 21, 1956
Drilling Completed: January 8, 1957

N. Suiter #A-1 - SE/4
Section 21-24S-14W, Stafford
County, Kansas.

DRILLERS LOG

Depth Figures Indicate Base of Formation

Sand & Clay	90
Shale & Shells	295
Shale	300
Red Bed & Sand	715
Red Bed & Shale	930
Anhydrite	960
Shale & Shells	1850
Shale & Lime Streaks	1900
Lime	2025
Lime & Shale	2370
Shale & Shells	2585
Lime & Shale	2800
Shale & Lime Streaks	2970
Shale & Lime	3470
Lime & Shale	3675
Shale & Lime	3735
Lime & Shale	3767
Lime	3950
Shale & Lime	4035
Lime, Shale, & Chert	4080
Lime & Chert	4085
Lime w/Chert	4091
Shale & Sand	4138
Chert	4208
Chert & Lime	4255
Shale & Lime	4283
Arbuckle	4287
Lime	4322 TD

I, Frank E. Stickle, hereby certify the above to be a true and complete Driller's Log of Sunray Mid-Continent Oil Company's N. Suiter #A-1 - SE/4 of Section 21-24S-14W, Stafford County, Kansas.

Frank E. Stickle

Frank E. Stickle

Lillian T. Bonham

Notary Public

February 13, 1960
My Commission Expires

REC
STATE CORPORATION COMMISSION

PLUGGING JAN

FILE SEC 21 24 14W

BOOK PAGE 132

CONSERVATION DIVISION
Wichita, Kansas