

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Drby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-185-19258-0000

API NUMBER N/A
LEASE NAME KOELSCH
WELL NUMBER 2
SPOT LOCATION c N/2 S/2 SW/4
SEC. 23 TWP. 24 SRGE. 14 W(E) or (W)
COUNTY Stafford
Date Well Completed 2/20/63
Plugging Commenced 7/25/85
Plugging Completed 7/25/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel and Gussman
ADDRESS 3232 First National Tower - Tulsa, OK 74103

PHONE # (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist. #1 - Dodge City, Kansas

Is ACO-1 filed? N/A If not, is well log attached? yes

Producing formation Lansing-K.C. Depth to top 3730' bottom 3767' T.D. 4260'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing-K.C.	depleted (oil)	3730	67	8-5/8	221	none
				5-1/2	4165	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Sanded back to 3680'; shot off 2016' of 5 1/2"; squeezed 200# hulls, 10 sx gel, 50 sx cement; then 10 sx gel, 100# hulls and 125 sx cement. Max. Press. 900#; SIP 400#
All cement used was 50/50 Poz with 6% gel and 3% CaCl.
Witnessed by state plugger, J. H. Metz.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company License No. _____
Address Box 31 - Russell, Ks. 67665

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M. R. Taylor (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *M. R. Taylor*
3232 First National Tower
(Address) Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 2nd day of August, 19 85

My Commission expires: 5/11/87

Mildred RECEIVED
STATE CORPORATION COMMISSION

AUG 5 1985
Form CP-4
Revised 01-84
CONSERVATION DIVISION

D R I L L E R S L O G#2 Koelsch

CASING RECORD: 214' of used 8-5/8" casing	COMPANY: Nadel and Gussman	DESCRIPTION: C/N2 S/2 SW/4 Sec. 23-24-14W Pratt County, Kansas
TOTAL DEPTH: 4260'	CONTRACTOR: Strata Drilling, Inc.	ELEVATION: 1931' RB
	COMMENCED: February 8, 1963	
	COMPLETED: February 20, 1963	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>	
Sand	0	80	Ran 214' of used 8-5/8" surface casing; set and cemented at 221' with 215 sacks of regular cement, 2% gel and 2% C. C. . Plug down at 3:00 P. M. February 9, 1963.	
Shale & Red Bed	80	222		
Red Bed & Shale	222	822		
Anhydrite	822	850		
Shale	850	860		
Shale & Lime	860	1650		
Shale w/Lime Streaks	1650	1940		
Lime & Shale	1940	2510		
Shale	2510	2770		
Shale & Lime	2770	3604		
Lime	3604	3845		
Lime & Shale	3845	3905		Ran six drill stem tests.
Lime	3905	3973		
Shale Chert	3973	4087		
Chert	4087	4120		
Lime & Shale	4120	4178	Ran Welex Log.	
Lime	4178	4260		


Total Depth 4260'

Ran 134 joints of 5 1/2" pipe; set and cemented at 4165' with 185 sacks of 60-40 posmix, 12% salt. Plug down at 10:15 P. M. February 20, 1963.


STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.


Jim B. McWilliams, Secy-Treas.

Subscribed and sworn to before me this 21st day of February, 1963.


Elaine H. Taylor, Notary Public

My Commission Expires:
December 14, 1965

RECEIVED
STATE CORPORATION COMMISSION

AUG 5 1985

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 5 1985

CONSERVATION DIVISION
Wichita, Kansas

100-100000-100000

RECEIVED