

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Stafford County, Sec. 23 Twp. 24 Rge. 14 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW SE NW

Lease Owner Hilton Drilling Company, Inc.

Lease Name Koelsch "B" Well No. 1

Office Address 2421 Tenth Street, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed 3-19-53 19

Application for plugging filed 3-19-53 19

Application for plugging approved 3-19-53 19

Plugging commenced 3-19-53 19

Plugging completed 3-19-53 19

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Rives

Producing formation Depth to top Bottom Total Depth of Well 4294 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	4210	2589
				8 5/8"	250	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with sand from 3670 to 3640 and ran 5 sacks of cement. Pumped in 25 bbls. of mud and 70 sacks of cement. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Chase, Kansas and

Address Globe Oilwell Cementing Company, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss. I, Henry Peacock, (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Henry Peacock

2421 Tenth St., Great Bend, Kansas


(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of March, 1953

Margaret Whitman Notary Public.

My commission expires April 4, 1956

24-2675-8 2-52-20M



3-26-53

DRILLER'S LOG

COMPANY: HILTON DRILLING COMPANY, INC. LOCATION: NW SE NW 23-24-14
 CONTRACTOR: HILTON DRILLING COMPANY, INC. Stafford County,
 Kansas
 FARM NAME: KOELSCH "B" NO. 1 ELEVATION: 1933 D.F.
 COMMENCED: 2-5-53
 COMPLETED: 2-25-53

Casing Used: 8-5/8" set @ 252' w/200 sacks
 5-1/2" set @ 4209' w/150 sacks

Clay, sand and gravel	40
Sand and clay	90
Shale	230
Red Bed	250
Red Bed, shale and shells	735
Red Bed	825
Anhydrite	850
Shale and shells	1650
Lime and shale	1820
Lime	2355
Lime and shale	2870
Lime - Broken	2935
Lime	2970
Broken lime and shale	3005
Lime and shale	3105
Lime	3544
Shale and lime	3624
Lime	3932
Conglomerate	3982
Mississippian	3985
Lime, chert and shale	4074
Chert and lime	4135
Chert	4148
Chert and lime	4185
Lime and shale	4212
Lime	4294
Total Depth	4294

TOPS:

Heebner	3462	-1527
Brown Lime	3596	-1661
Lansing	3623	-1688
Arbuckle	4209	-2274

RECEIVED
 STATE COMMISSION

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

PLUGGING
 FILE SEC 23-24-14W
 BOOK PAGE 26 LINE 24

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

HILTON DRILLING COMPANY, INC.

Henry Peacock
 Henry Peacock, Secretary

Subscribed and sworn to before me this 27th day of February, 1953.

My commission expires: 4-4-56

Margaret Coleman
 Notary Public