

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER N/A

LEASE NAME KOELSCH

WELL NUMBER 3

SPOT LOCATION ec W/2 NE SW

SEC. 23 TWP. 24 SRGE. 14 W(E) or (W)

COUNTY Stafford

Date Well Completed 10/8/64

Plugging Commenced 7/25/85

Plugging Completed 7/25/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel and Gussman

ADDRESS 3232 First National Tower - Tulsa, OK 74103

PHONE # (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist. #1 - Dodge City, Kansas

Is ACO-1 filed? N/A If not, is well log attached? yes

Producing formation Lansing-K.C. Depth to top 3742' bottom 3747' T.D. 4194'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing-K.C.	depleted (oil)	3742	47	8-5/8	208	none
				5-1/2	4200	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Down 5 1/2", 400# hulls, 50 sx cement and 10 sx gel; then 100# hulls and 150 sx cement.

Max. Press. 800#; SIP 800#

All cement used was 50/50 Poz with 6% gel and 3% CaCl.

Witnessed by state plugger, J. H. Metz

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company License No. _____
Address Box 31 - Russell, Ks. 67665

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M. R. Taylor (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M.R. Taylor
3232 First National Tower
(Address) Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 2nd day of August, 1985

RECEIVED Richard Carter
STATE CORPORATION COMMISSION Notary Public

My Commission expires: 5/11/87

AUG 5 1985

ROTARY DRILLERS' LOG

OPERATOR: Nadel & Gussman
625 Union Center
Wichita, Kansas

DRILLING COMMENCED: 9-28-64

CONTRACTOR: Graves Drilling Co., Inc.
412 Union Center
Wichita, Kansas

DRILLING COMPLETED: 10- 8-64

CASING RECORD: 7 Jts. 208'-8-5/8"
cemented with 225 sacks

130 Jts. 4200-5 1/2"
cemented with 160 sacks


LOCATION: Koelsch No. 3
C W/2 NE SW
Section 23-24S-14W
Stafford County, Kansas

0 - 200	Shale & sand	3614 - 3856	Lime
200 - 824	Shale	3856 - 3993	Lime & shale
824 - 843	Anhydrite	3993 - 4001	Chert & lime
843 - 1930	Shale & shells	4001 - 4008	Lime
1930 - 2089	Lime & shale	4008 - 4043	Shale & lime
2089 - 2250	Lime	4043 - 4085	Chert & lime
2250 - 2530	Lime with shells	4085 - 4131	Lime with chert
2530 - 2882	Shale & lime	4131 - 4162	Lime
2882 - 3000	Lime	4162 - 4171	Lime & shale
3000 - 3340	Lime & shale	4171 - 4194	Lime
3340 - 3409	Lime	4194	Rotary Total Depth
3409 - 3614	Lime with shale		

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By *John Graves*
President



Subscribed and sworn to before me, a Notary Public, this 14th day of October, 1964.

(My commission) expires:

April 30, 1967

Betty Brandt
Betty Brandt Notary Public

Copy to Conservation Commission
Copy to Well Log Review

RECEIVED
STATE CORPORATION COMMISSION

AUG 5 1965

CONSERVATION DIVISION
Wichita, Kansas