

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-185-00299-0001

API NUMBER N/A
LEASE NAME KOELSCH
WELL NUMBER 1
SPOT LOCATION SE SE SW
SEC. 23 TWP. 24 SRGE. 14 W (E) or (W)
COUNTY Stafford
Date Well Completed 3/25/59
Plugging Commenced 7/25/85
Plugging Completed 7/25/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel and Gussman
ADDRESS 3232 First National Tower - Tulsa, OK 74103
PHONE # 918, 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Injection
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist. #1 - Dodge City, Kansas

Is ACO-1 filed? N/A If not, is well log attached? yes

Producing formation Lansing-K.C. Depth to top 3738' bottom 3742' T.D. 4232'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing-K.C.	saltwater	3738	42	8-5/8	215	none
				5-1/2	4044	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped down 5 1/2", 25 sx cement, 100# hulls; then 10 sx gel, 75 sx cement.
Max. Press. 900#; STP 400# Pumped down 8-5/8" annulus, 75 sx cement @ 100# max.
All cement used was 50/50 Poz with 6% gel and 3% CaCl.
Witnessed by state plugger, J. H. Metz.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company License No. _____
Address Box 31 - Russell, Ks. 67665

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M. R. Taylor (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) MR Taylor
3232 First National Tower
(Address) Tulsa, OK 74102

SUBSCRIBED AND SWORN TO before me this 2nd day of August, 1985

My Commission expires: 5/11/87

REC'D
Dorothy Carter
STATE CORPORATION COMMISSION Notary Public

AUG 5 1985

Nadel and Gussman

Koelsch No. 1

SE SE SW 23-24-14W
Stafford County, Kans

Comm: 3-13-59

Comp: 3-25-59

Casing 8-5/8" 215' w/150 sax
5-1/2" 4044' w/125 sax

Formations

Depths

Shale and sand	215
Shale	250
Shale and red bed	835
Anhydrite	860
Shale and shells	1825
Lime and shale	2555
Shale and shells	2740
Shale	2955
Shale and lime	3100
Shale	3245
Lime and shale	3340
Lime	3390
Lime and shale	3612
Lime	3940
Lime and chert	3982
Lime	4065
Lime and chert	4100
Lime	4135
Lime and shale	4170
Lime	4232

Geological Tops

Heebner	3452
Brown Lime	3585
Lansing	3612
Base Kansas City	3884
Mississippi	3935
Kinderhook	3983
Viola	4040
Simpson	3168
Arbuckle	4221

STATE OF KANSAS)
(SS:
COUNTY OF SEDGWICK)

L. C. Hay, of lawful age, states that the above formations and depths are correct to his best knowledge.

Subscribed and sworn to before me this 30th day of March, 1959.

L. C. Hay

[Signature]

Notary Public

My commission expires Nov. 3, 1960

RECEIVED
STATE CORPORATION COMMISSION

AUG 5 1965

CONSERVATION DIVISION
Wichita, Kan.