

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Stafford County. Sec. 24 Typ. 24S Rge. 14 (E) W (W)
 Location as "NE/CNW/WSW" or footage from lines. SW/4 SW/4 NW/4
 Lease Owner Glickman Oil Company
 Lease Name Mason Well No. 1
 Office Address P. O. Box 3108, 702 South St. Francis, Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed December 11, 19 54
 Application for plugging filed (verbal) December 11, 19 54
 Application for plugging approved (verbal) December 11, 19 54
 Plugging commenced December 11, 19 54
 Plugging completed December 11, 19 54
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives
 Producing formation Depth to top Bottom Total Depth of Well 4255 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	231'	8-5/8"	231'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug and bridge set at 230' and 20 sacks of cement displaced through drill pipe. Top bridge and plug set at 35' and 10 sacks of cement mixed and dumped into surface casing, filling up to base of cellar.

12-15-54

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Birmingham-Bartlett Drilling Co.
 Address 300 Kaufman Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
 Richard Hindery, partner of Birmingham-Bartlett Drilling Co., contractor (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. BIRMINGHAM-BARTLETT DRILLING CO.

(Signature) By Richard Hindery Partner
 300 Kaufman Bldg., Wichita 2, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of December, 19 54

My commission expires October 2, 1958

Beverly Larson
 Notary Public.

PLUGGING
 FILE DEC 24 1954
 BOOK PAGE 24 LINE 35

MASON NO. 1 WELL

LOCATION: SW/4 SW/4 NW/4
Section 24-24S-14W
Stafford County, Kansas

SPUDED: 11-27-54
COMPLETED: 12-11-54

LEASE OWNER: Glickman Oil Company
702 South St. Francis
P. O. Box 3108
Wichita, Kansas

CONTRACTOR: Birmingham-Bartlett Drilling Co.
300 Kaufman Bldg.
Wichita 2, Kansas

SURFACE CASING: 8-5/8" 24# casing cemented at 231' with
175 sacks cement and 3 cc.

OIL STRING: None set. Dry and abandoned.

LOG

(Figures indicate bottom of formation)

0	56	Sand
	85	Shale and sand
	90	Sandstone
	400	Shale and shells
	820	Red bed
	850	Anhydrite
	1795	Shale and shells
	2035	Broken lime
	2520	Lime and shale
	2875	Shale and shells
	3255	Lime and shale
	3435	Lime
	3657	Shale and lime
	3880	Lime
	3975	Lime and shale
	4020	Conglomerate
	4043	Conglomerate and viola
	4072	Lime
	4093	Viola lime
	4171	Chert and lime
	4223	Shale and sand
	4255	Lime
	4255	RTD - D & A

The undersigned, Richard Hindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the formations encountered in drilling the Mason No. 1 Well as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery

Subscribed and sworn to before me
this 13th day of December, 1954.

Beverly Larson
Notary Public

My commission expires October 2, 1958

PLUGGING
WELL SEC 24 T 24 R 14 W
PAGE 34 LINE 35