

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 24 Twp. 24S Rge. 14 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE NW

Lease Owner Hilton Drilling Company, Inc.

Lease Name Luty Well No. 1

Office Address 2421 Tenth Street, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed March 25 19 54

Application for plugging filed March 24 19 54

Application for plugging approved March 24 19 54

Plugging commenced March 25 19 54

Plugging completed March 25 19 54

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4231 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
					212'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from total depth to 210'. Plug set at 210'. Hole filled with 20 sx cement from 210' to 40'. Top plug set at 40'. Hole filled from 40' to surface with 10 sx. cement. Cement circulated through drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Hilton Drilling Company, Inc.

Address P. O. Box 108, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Henry Peacock, Secretary (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Henry Peacock  
2421 Tenth Street, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of March, 1954

My commission expires April 4, 1956.

Margaret Whitson Notary Public.

PLUGGING  
FILE SEC 24 T 24 S 14 W  
BOOK PAGE 23 LINE 4

4-9-54

DRILLER'S LOG

COMPANY: Hilton Drilling Company, Inc. LOCATION: NE NE NW  
 Sec. 24-24S-14W  
 CONTRACTOR: Hilton Drilling Company, Inc. Stafford County  
 Kansas  
 FARM NAME: Luty #1 ELEVATION: 1929 KB  
 COMMENCED: March 10, 1954 CASING USED: 8-5/8"@212' w/225 sx.  
 COMPLETED: March 25, 1954

Clay	10	
Sand	75	
Shale	165	
Sand	185	
Shale	225	
Red Bed	290	
Sand	310	
Red Bed	800	
Anhydrite	827	
Shale and Shells	1060	
Shale, Shells and Salt	1490	
Shale and Lime	1755	
Lime	2135	
Sand	2155	
Lime	2175	
Lime and Shale	2845	
Shale	2878	<u>TOPS</u>
Lime and Shale	3155	
Lime	3495	Heebner 3430
Shale and Lime	3566	Br. Lime 3566
Lime	3845	Lansing 3590
Lime and Shale	3913	Mississippi 3920
Conglomerate	3926	Kinderhook 3945
Lime, Shale and Chert	4027	Viola 4003
Lime and Chert	4157	Simpson Shale 4157
Shale, Lime and Sand	4185	Arbuckle 4211
Lime, Shale and Chert	4225	
Lime	4231	
TOTAL DEPTH	4231	

STATE OF KANSAS )  
 ) ss  
 COUNTY OF BARTON )

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

**PLUGGING**  
 FILE SEC 24 T 24 R 14W  
 BOOK PAGE 23 LINE 4

HILTON DRILLING COMPANY, INC.

*Henry Peacock*  
 Henry Peacock, Secretary.

Subscribed and sworn to before me this 25<sup>th</sup> day of March, 1954.

**RECEIVED**  
 STATE COMMISSION  
 APR 2 1954  
*Margaret Whitmore*  
 Notary Public

My commission expires 4-4-56

STATE COMMISSION