

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 129-23

LOCATION new-new-71E

SEC. 27 TWP. 14 RGE. 14-00

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Neill

Operator The Atlantic Refining Co. Address Box #17 G. Bend-Kans.

Field _____ County Stafford

Total Depth 4240 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 499 ft. Circulated with cement.
5 1/2 casing set at 4225 ft. - 200 sacks of cement. Plugged
back with sand to 4060 ft. - Drilled 5 sacks of cement
at 4060 ft. Shot off & killed the 5 1/2 casing - Pumped in
50 sacks of mud the Plug x 200 sacks of cement
filling hole from 420 ft to the surface with cement.

Cement & mud Pumped in by Halliburton -
Jack Patterson - Plugging Contractor

PLUGGING
FILE SEC 27 T 14 R 14-00
PAGE 129 OF 13

JAN 31 1952

C. H. Stough -
District Conservation Agent

Date 1-29-52