

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 129-24

LOCATION C-NW-SW-NE

SEC. 27 TWP. 24 RGE. 14-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Neill

Operator The Atlantic Refining Co. Address Box #17 - St. Bend, Kans

Field _____ County Stafford

Total Depth 4209 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2 - 882 ft. Circulated with cement.
5 1/2 casing out at 4200 ft. - 175 sacks of cement. Plugged
back to 3876 ft. with cement. Filled hole with sand to 3800 ft.
Dumped 5 sacks of cement at 3800 ft. Shot off & killed the
5 1/2 casing - mud to 175 ft. Set Rock Bridge & 20 sacks of
cement at 175 ft. mud to 35 ft. Bridge &
10 sacks of cement at the surface

J.M. Patterson & Son - Plugging Contractors

STATE OF KANSAS
JAN 19 1952

CONC.
C. W. Storch
District Conservation Agent

Date 1-17-52

PLUGGING
FILE NO. 27 24 R 14 W
BOOK PAGE 129 LINE 24