

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION

JUN 29 1964

CONSERVATION DIVISION
Wichita, KansasOperator's Full Name D. R. Lauck Oil Co., Inc.Complete Address: 301 South Broadway, Wichita, KansasLease Name Suiter Well No. # B-1Location NW NW NW Sec. 21 Twp. 24 Rge. 14 (E) (W) WCounty Stafford Total Depth 4305Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Glen & Smith Casing Pulling Co.Address: 204 East Sixth St., Ellinwood, Kansas License No. 396Operation Completed: Hour 11:00AM Day 27th Month June Year 1964

The Above well was plugged as follows:

215' of 8 5/8" surface pipe, cement circulated. 4299' of 5 1/2" long string,
cemented with 100 sacks. Bottom of the hole was sanded to 4290', and cem-
ented with 5 sacks. Fluid level was up in the hole. Plug was pushed to
200', with 10' of rock bridge. 6 sacks of cement was mixed in barrel and
put on plug, through dump bailer and let set over night. Next morning
hole bailed down, and 19 sacks of cement was added to the plug. Hole
was filled with mud to 40', with 10' of rock bridge, and cemented with
10 sacks to base of the cellar. 3130' of 5 1/2" long string was recovered
from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 6/29/64INV. NO. 9382-W