

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Icer Addis
Complete Address 312 Petrol Bldg Wichita, KS
Lease Name Koelsch Well No. 6
Location SE/NW/SW Sec. 24 Twp. 24 Rge. 14 (E) (W) W
County Stafford Total Depth 3900
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Knight Casing Pulling Co Inc
Address Box 405 Chase, KS License No. 436
Operation Completed: Hour 2:00 PM Day 15 Month 1 Year 1973

The above well was plugged as follows:
832 ft 8 5/8 surface cemented with 500 sacks. 3899 ft 5 1/2 long string
cemented with 125 sacks. Plug back to 3715 ft. Top perf. 3688 ft.
Sand to 3650 ft, 5 sacks cement with bailer. Pulled 2735 ft 5 1/2. Set
10 ft rock bridge at 360 ft. Fill hole with 6 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 1/17/73
INV. NO. 6869-W