

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217RECEIVED
STATE CORPORATION COMMISSION
FEB 12 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Icer Addis

Complete Address 312 Petroleum Bldg Wichita, KS

Lease Name Koelsch Well No. 2

Location NE/SW/SW Sec. 24 Twp. 24 Rge. 14 (E) (W) W

County Stafford Total Depth 3890

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co. Inc

Address Box 405 Chase, KS License No. 436

Operation Completed: Hour 2:00 PM Day 9 Month 2 Year 1973

The above well was plugged as follows:

843 ft 8 5/8 surface cemented with 500 sacks. 3889 ft 5 1/2 long string
cemented with 125 sacks. Top perf. 3684 ft. Sand to 3650 ft, 5 sacks
cement with bailer. Pulled 2840 ft 5 1/2. Set 10 ft rock bridge at
360 ft. Fill hole with 6 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *A. Russell Bicksten*

Well Plugging Supervisor

DATE 2/12/73INV. NO. 6960-4