

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1964

CONSERVATION DIVISION
Wichita, Kansas

08-10-64

Operator's Full Name D. R. Lauck Oil Co., Inc.

Complete Address: 301 S. Broadway, Wichita, Kansas

Lease Name Mason Well No. # 1

Location SE NW NE Sec. 24 Twp. 24 Rge. 14 (E) (W)W

County Stafford Total Depth 4043

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glen & Smith Casing Pulling Co.

Address: 204 East Sixth St., Ellinwood, Kansas License No. 396

Operation Completed: Hour 11:00 AM Day 7th Month August Year 1964

The Above well was plugged as follows:

223' of 8 5/8" surface pipe, cement circulated. 4043' of 5 1/2" long string,
top of cement 3700'. Plug back to 4015'. Top perforation 3935'. Plug
was pushed to 3920, bridged with sand, and cemented with 4 sacks. Fluid
level was up in the hole. Cementing plug was pushed in fluid to 215',
bridged with 10' of rock. 5 sacks of cement was mixed in barrel and put
on plug through dump bailer, and let set over night. Next morning hole
bailed down, and 20 sacks of cement was added to the plug. Hole was fill-
ed with mud to 40', 10' of rock bridge, and cemented with 10 sacks to base
of cellar. 2870' of 5 1/2" long string was recovered from the hole.
I hereby certify that the above well was plugged as herein stated.

DATE 8/10/64
INV. NO. 9619-W

Signed: Archie Elving
Well Plugging Supervisor