

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
OCT 5 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Icer Addie

Complete Address Drawer 8038 Wichita, KS

Lease Name Koelsch Well No. 7

Location SE/SW/SW Sec. 24 Twp. 24s Rge. 14 (E) (W) W

County Stafford Total Depth 3900

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co Inc

Address Box 405 Chase, KS License No. 436

Operation Completed: Hour 1:00 PM Day 3 Month 10 Year 1973

The above well was plugged as follows:

758 ft 8 5/8 surface cemented with 500 sacks. 3899 ft 5 1/2 long string
cemented with 125 sacks. Top perf. 3747 ft. Sand to 3700 ft, 5 sacks
cement with bailer. Pulled 2900 ft 5 1/2. Set 10 ft rock bridge at
350 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 10/5/73

INV. NO. 4987-10