

KANSAS

Form CP-3  
Rev. 6-4-68

15-185-11022-0000

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

OCT 5 1973

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Addis Oil Operations

Complete Address 5307 E. Central Wichita, KS

Lease Name Koelsch Well No. 4

Location NW/SW/SW Sec. 24 Twp. 24 Rge. 14 (E) (W) W

County Stafford Total Depth 3905

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co Inc

Address Box 405 Chase, KS License No. 436

Operation Completed: Hour 2:00 PM Day 3 Month 10 Year 1973

The above well was plugged as follows:

844 ft 8 5/8 surface cemented with 500 sacks. 3904 ft 5 1/2 long string

cemented with 125 sacks. Open hole. Sand to 3800 ft, 5 sacks cement

with bailer. Pulled 2824 ft 5 1/2. Set 10 ft rock bridge at 350 ft.

Fill hole with 5 yds redimix to surface.

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

I hereby certify that the above well was plugged as herein stated.

Signed *W. Russell B. Hunter*  
Well Plugging Supervisor

INVOICED

DATE 10/5/73

INV. NO. 7986-10