

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JAN 19 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Icer Addis
Complete Address 312 Petroleum Bldg Wichita, KS
Lease Name Koelsch Well No. 5
Location SW/NW/SW Sec. 24 Twp. 24 Rge. 14 (E) W
County Stafford Total Depth 3895
Abandoned Oil Well X Gas Well Input Well X SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Knight Casing Pulling Co Inc
Address Box 405 Chase, KS License No. 436
Operation Completed: Hour 11:00 AM Day 18 Month 1 Year 1973

The above well was plugged as follows:

831 ft 8 5/8 surface cemented with 500 sacks. 3894 ft 5 1/2 long string
cemented with 125 sacks. Plug back to 3785 ft. Top perf. 3676 ft,
Sand to 3650 ft, 5 sacks cement with bailer. Pulled 2800 ft 5 1/2. Set
10 ft rock bridge at 360 ft. Fill hole with 6 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 1-19-73INV. NO. 6842-W