



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 92-10

LOCATION CE4-18W-2E-

SEC. 16 TWP. 24 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease Equitable Life

Operator Huhns & Campbell Address 1405 Lockman St. A. Bend - Kans.

Field _____ County Stafford

Total Depth 3808 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 288 ft. Circulated with cement.
7" casing at 3806 - 6 sacks of cement dumped
on bottom of hole - Filled back with chat to 3270 ft.
dumped 6 sacks of cement at 3270 ft - Shot off & pulled
the 7" casing - Filled with mud to 280 ft - Rock bridge x
20 sacks of cement at 280 ft - Mud & Rock bridge x
10 sacks of cement at the surface

Hargrett & Lynch -
Plugging - Contractors

RECEIVED
Conservation Div.
MAY 12 1949
STATE OF KANSAS
C. O. Starnes
District Conservation Agent

Date 5-9-49

PLUGGING
FILE SEC. 15 T. 24 R. 11W
BOOK PAGE 92 LINE 10