

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 109-19LOCATION SW/2 - NE - NWSEC. 16 TWP. 24 RGE. 11-WDry Hole Abandoned Oil Well X Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 3 Lease M. HickpatrickOperator Stanolind Oil & Gas Co. Address Box #7 - Ellinwood - Kans.Field County StaffordTotal Depth 3827 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 261 ft. Circulated with cement.
5 1/2" casing set at 3820 ft. - Plugged back from bottom
to 3815 ft with chat - Dumped 5 sacks of cement
at 3815 ft. Ripped off & pulled the 5 1/2" casing
Filled with mud to 260 ft. Set Rock Bridge & 15 sacks
of cement at 260 ft. Mud to 30 ft. Plug & 10 sacks
of cement at the surface. Bill Morgan - Plugging Contractor

C. H. Stough -

District Conservation Agent

Date 8-27-49**PLUGGING**FILE SEC 15 T 24 R 11WBOOK PAGE 109 LINE 19**RECEIVED**

Conservation Div.

AUG 31 1949

STATE CORPORATION
COMMISSION
KANSAS

8-31-49