

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 78-16

LOCATION C 2 1/4 - SW - SE

SEC. 15 TWP. 24 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 7 Lease W. G. Farris

Operator Standard Oil & Gas Co Address Box #9 - Ellinwood - Kans.

Field _____ County Stafford

Total Depth 3830 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4 - 273 ft. Circulated with cement.
3 1/2 casing set at 3796 ft. Cemented with 100 sacks cement.
Plugged back to 3790 ft with chat - Dumped 5 sacks
of cement at 3790 ft. Shut off & pulled the 3 1/2 casing -
Weld to 273 ft. Set Rock Bridges & 15 sacks of cement
at 273 ft. Weld to 30 ft. Plug & 10 sacks of
cement at the surface.

Pipe Pulling, Inc. Plugging Contractor.

STATE CORPORATION COMMISSION

MAY 4 - 1951 5-4-51

CONSERVATION DIVISION

Wichita, Kansas
District Conservation Agent

Date 5-8-51

PLUGGING
FILE SEC. 15 TWP. 24 R. 11W
BOOK PAGE 78 LINE 16