

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 27-24

LOCATION CE 1/2 - NE - SE

SEC. 15 TWP. 24 RGE. 11-6

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease W. H. Ferris "A"

Operator Standard Oil & Gas Co Address Box #7, Ellinwood - Kansas

Field _____ County Stafford

Total Depth 3899 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 10 3/4 - 260ft - Circulated with cement.
4 1/2" casing set at 3795ft. Cemented with 100 sacks cement
Plugged back to 3780ft. with cement - Mixed 6 sacks
of cement at 3780ft - Ripped off & pulled the 5 1/2" casing -
Filled with mud to 260ft. Set Rock Bridge &
20 sacks of cement at 260ft. Mixed to 20ft - Bridge
& 10 sacks of cement at the surface
John M. Walker - Plugging Contractor*

RECEIVED
STATE CORPORATION COMMISSION

9-30-50

SEP 30 1950

CONSERVATION DIVISION
Wichita, Kansas

C. M. Strong
District Conservation Agent

Date 9-28-50

PLUGGING
FILE SEC. 15 TWP. 24 R. 11W
BOOK PAGE 27 LINE 24