

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 25-15

LOCATION SE-SE-SE

SEC. 15 TWP. 14 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease M. H. Ferris - "A"

Operator Fairland Oil & Gas Co. Address Box #7, Ellinwood - Kansas

Field _____ County Stafford

Total Depth 3831 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 254 ft. Circulated with cement
6" casing at 3801 ft. cemented - Plugged back to
3790 ft with shot - Pumped 6 sacks of cement at
3790 ft - Shot off & pulled the 6" casing - Filled with
Mud to 254 ft - Set Rock Bridge & 20 sacks of cement
at 254 ft - Set Rock Bridge & 20 sacks of cement
at the surface - Heavy Mud between plugs
Miller Casting Pulling Co. Plugging Contractor

RECEIVED
STATE CORPORATION COMMISSION
9-25-50

PLUGGING
SEP 25 1950
FILE SEC 15 T CONSERVATION DIVISION
Wichita, Kansas
BOOK PAGE 25 LINE 15

E. C. Stough
District Conservation Agent
Date 9-23-50