

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 63-42

LOCATION C5/2-SW-SW

SEC. 3 TWP. 24 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease L.S. Healey

Operator Wm. James W. Morgan Address 7102 W. 18th St. Hutchinson - Kas.

Field _____ County Stafford

Total Depth 3756 3843 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 1 3/4 - 4.5 ft Circulated with cement.
7' casing at 3746 ft. Cemented with 145 sacks cement.
Plugged back to 3736 ft with chert. Dumped 6 sacks of
cement at 3736 ft. Mud to 3430 ft. Back bridge & 6 sacks
of cement - picked off & pulled the 7' casing - mud to 250 ft
Set back bridge & 20 sacks of cement at 250 ft and
to 30 ft. Plug & 10 sacks cement at the surface
Bill Morgan - Plugging Contractor*

RECEIVED
STATE CORPORATION COMMISSION
MAR - 5 1951
CONSERVATION DIVISION
Wichita, Kansas

3-5-51

Ed. [Signature]
District Conservation Agent

Date 3-2-51

PLUGGING
FILE SEC 3 T 24 R 11
BOOK PAGE 63 LINE 42