

R

DISTRICT CONSERVATION AGENT'S REPORT

RECEIVED
Conservation Div.
OCT 21 1949
STATE CORPORATION
COMMISSION
KANSAS

10-21-49

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 117-4

LOCATION E/2 - SE - NW

SEC. 3 TWP. 24 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Buckles

Operator Great Lakes Carbon Corp Address 501 Petroleum Bldg, Wichita - Kans.

Field _____ County Stafford

Total Depth 3730 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/8 = 324 ft. Circulated with cement
5 1/2 casing set at 3700 ft. Plugged back from bottom
to 3700 ft with cement - Mounded 15 sacks of cement at 3700 ft.
Drilled off & pulled the 5 1/2 casing - filled with mud to
300 ft. Set Rock Bridge & 15 sacks of cement at 300 ft.
Mud to 30 ft. Bridge & 15 sacks of cement at the surface.
Bill Morgan - Plugging Contractor

C. M. Stough
District Conservation Agent

Date 10-19-49

PLUGGING
FILE SEC 3 T 24 R 11 W
BOOK PAGE 117 LINE 4