


DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 117-5

LOCATION 7E4 - CEL SW NE

SEC. 3 TWP. 24 RGE. 11

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Johnson

Operator Great Lakes Carbon Corp Address 501 Petroleum Bldg - Wichita - Kans.

Field \_\_\_\_\_ County Stafford

Total Depth 3735 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 243 ft - Circulated with cement  
Old 5 1/2" casing set at 3693 ft - Plugged back from  
bottom to 3690 ft with chat - Mixed 5 sacks of  
cement at 3690 ft - Ripped off & pulled the 5 1/2" casing -  
Filled with mud to 243 ft - Set back bridge &  
15 sacks of cement at 243 ft - Mud to 36 ft - Plug  
& 10 sacks of cement at the **RECORDED**

Bill Morgan - Plugging Contractor Contractor's Initials

OCT 15 1949

District Conservation Agent  
COMMISSION

Date 10 - KANSAS

10-15-49

**PLUGGING**  
FILE SEC 3 TWP 24 RGE 11  
NOV 17 1949