

15-155-01662-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Reno SEC. 1 TWP. 23 RGE. 4 R/W.
 Location as in quarters or footage from lines:
330' N of S Line 330' East of W. Line NW/4

Lease Owner Harold J. Milburn
 Lease Name Haury Well No. 2
 Office Address 7315 N Monroe Hutchinson, Kansas 67502
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed April 11, 1958
 Application for plugging filed June 5, 1985
 Plugging commenced July 2, 1985
 Plugging completed July 3, 1985
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Injection well not needed
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Johnny Sanders
 Producing formation Mississippi Depth to top 3247 bottom 3500 T.D. 3613
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record


Formation	Content	From	To	Size	Put in	Pulled Out
<u>Mississippi</u>	<u>Water</u>	<u>3247</u>	<u>3500</u>	<u>5 1/2</u>	<u>3601</u>	<u>400'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set. Bridge plug set @ 3350. Sanded casing to 3250
Dumped 6 sacks cement on top of sand. Shot off 5 1/2 casing @ 400'. Pushed rubber plug
down surface pipe to 400' Put in 30' of sand on plug. Filled to top with 6 3/4 yards
of redi mix cement. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gressel Oil Field Service, Inc.

STATE OF Kansas COUNTY OF Reno, ss. _____ and
Harold J. Milburn (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.



(Signature) Harold J. Milburn
7315 N Monroe Hutchinson, Ks.
 (Address) 67502

SUBSCRIBED AND SWORN TO before me this 8th day of July, 19 85

My Commission expires: Feb. 1-1987

Verna E. Milburn
 RECEIVED Notary Public.
 STATE CORPORATION COMMISSION

DRILLERS LOG
 TOMLINSON-KATHOL, INC.
 # 2 HAURY
 SW SW NE~~W~~ SEC. 1-23S-4W
 RENO COUNTY, KANSAS.

15-155-01662-0000

Contractor - Tomlinson-Kathol, Inc.

Elevation - 1469 KB
 Commenced - 2/17/58
 Completed - 3/2/58

<u>From</u>	<u>To</u>	<u>Description</u>	<u>Remarks</u>
0	170	Sand & clay	
170	200	Rock & sand	
200	250	Rock & shale	
250	455	Shale	
455	600	Salt & shale	
600	647	Lime & Shale	8-5/8" @ 662 w/400 sks cement
730	1175	Shale & shells	
1175	1600	Shale	
1600	2045	Shale & lime streaks	
2045	2441	Shale	
2441	2583	Shale & lime	
2583	2720	Lime	
2720	2826	Shale & lime	
2826	3247	Lime	
3247	3494	Lime & chert	
3494	3600	Shale	
3600	3601	Lime	Mississippi 3247
3601		Rotary Total Depth	Hunton 3601
			5-1/2" @ 3601

I certify that to the best of my knowledge and belief, the above represents a true and accurate Driller's Log record of the captioned well.

Warren E. Tomlinson
 Warren E. Tomlinson

State of Kansas)
)
 County of Sedgwick)

Subscribed and sworn to before me this 19th day of June, 1958.

Notary Public

My commission expires Jan. 19, 1961.

Rec'd
 7-19-85

RECEIVED
 STATE CORPORATION COMMISSION

F111 10
 CONSERVATION DIVISION
 Wichita, Kansas