

LEASE NAME Haury

WELL NUMBER 4

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 1 TWP. 23 RGE. 4W (52) or (W)

COUNTY Reno

Date Well Completed         

Plugging Commenced 2-20-95

Plugging Completed 2-22-95

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Coas. Div.  
office within 30 days.

LEASE OPERATOR Harold J. Milburn

ADDRESS 7315 N. Monroe Hutchinson, Ks. 67502

PHONE#(316) 663-1616 OPERATORS LICENSE NO. 5526

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by          (KCC District Agent's Name).

Is ACO-1 filled?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 3400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				12 3/4"	310'	none
				4 1/2"	3398'	2035'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug are used, state the character of same and depth placed, from          feet to          feet each set  
Sanded bottom to 3340' ran 4 sacks cement. Shot @2035'. Pulled to 600' pumped 35  
sacks cement 200# hulls, pulled to 350' circulated to top with 200 sacks, topped  
off with 50 sacks 60/40 4% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Harold J. Milburn

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P.O. Box 209 Chase, Kansas 67524


SUBSCRIBED AND SWORN TO before me this 23 day of February, 19 95

*Irene Herzberg*  
Notary Public

My Commission Expires:  
USE ONLY ONE SIDE OF EACH FORM



STATE CORPORATION COMMISSION  
RECEIVED  
FEB 24 1995



# Blackstone Drilling, Inc.

Box 455 523 West Kansas Phone (316) 241-1250

McPHERSON, KANSAS 67460

August 25, 1981

15-155-20421-0000

**COMPANY:** HAROLD J. MILBURN  
**CONTRACTOR:** BLACKSTONE DRILLING, INC.  
**FARM:** HAURY #4  
**LOCATION:** 440' WEL & 720' NSL SE NW Section 1-23-4W, Reno County, Kansas  
**COMMENCED:** August 18, 1981  
**COMPLETED:** August 22, 1981  
**ELEVATION:**

0	to	195	Sand
195	to	275	Shale & Sand
275	to	960	Shale
960	to	2020	Shale & Lime
2020	to	2170	Lime & Shale
2170	to	2560	Shale & Lime
2560	to	2885	Lime & Shale
2885	to	3190	Lime
3190	to	3325	Lime & Shale
3325	to	3400	Shale & Lime
		3400	T. D.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 28 1981  
REGISTRATION DIVISION  
TOPEKA, KANSAS

Cut 12 1/2" hole to 310' and run 312' pf 12 3/4" surface pipe, cemented with 210 sacks of cement at 310'. Plug down at 1:20 P. M., August 18, 1981. Run 3403' of 4 1/2" casing, cemented 2 feet off bottom at 3398'. Plug down at 11:30 P. M., August 22, 1981.

**TOPS:**

Measurements taken from K. B.

### CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Haury #4, located on the 440' WEL & 720' NSL SE/4 NW/4 Section 1-23-4W, Reno County, Kansas as reflected by the files of Blackstone Drilling, Inc.

P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 25th day of August, 1981.

Johnnie L. Schmidt - Notary Public

JOHNNIE L. SCHMIDT  
McPherson County, Kansas  
My Appt. Exp. June 23, 1982