

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-20604-0000

LEASE NAME Haury

WELL NUMBER 3

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 1 TWP. 23 RGE. 4W (W)

COUNTY Reno

Date Well Completed

Plugging Commenced 3-19-91

Plugging Completed 3-21-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Harold J. Milburn

ADDRESS 7315 N. Monroe Hutchinson, Ks. 67502

PHONE#(316) 663-1616 OPERATORS LICENSE NO. 5526

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3390'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	550'	none
				5 1/2"	3380'	2440'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 3300', ran 5 sacks cement. Shot @2440'.

Pulled up to 680' dumped 35 sacks cement, pulled up to 300'
circulated, pulled rest of pipe used 180 sacks cement, 300#
hulls.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Harold J. Milburn

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 27 day of March, 19 91

My Commission Expires:



Notary Public



Blackstone Drilling, Inc.

Box 1184 • 528 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

August 24, 1979

COMPANY: HAROLD J. MILBURN
CONTRACTOR: BLACKSTONE DRILLING, INC.
FARM: HAURY #3
LOCATION: SE SE NW Section 1-23-4W,
Reno County, Kansas
COMMENCED: August 17, 1979
COMPLETED: August 23, 1979
ELEVATION:

15-155-20604-0000

0	to	40	Sand
40	to	275	Clay & Sand
275	to	1110	Shale
1110	to	1445	Shale & Lime
1445	to	1910	Lime & Shale
1910	to	2525	Shale & Lime
2525	to	2835	Lime & Shale
2835	to	2980	Shale & Lime
2980	to	3390	Lime
	to	3390	T. D.

Cut 17 1/2" hole to 313' and run 315' of 12 3/4" surface casing, cemented with 200 sacks of cement at 313'. Plug down at 1:45 P. M., August 17, 1979. Run 617' of 8 5/8" casing, cemented with 75 sacks of cement at 550'. Plug down at 11:45 A. M., August 19, 1979. Cut 7 7/8" hole to 3390'. Run 3395' of 5 1/2" casing, cemented 2' off bottom at 3388'. Plug down at 7:15 P. M., August 23, 1979. Used 100 sacks of cement to cement the 5 1/2" casing.

TOPS:


Measurements taken from the K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Haury #3, located on the SE SE NW Section 1-23-4W, Reno County, Kansas as reflected by the files of Blackstone Drilling, Inc.


P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 24th day of August, 1979.


Johnnie L. Schmidt - Notary Public

