

WELL PLUGGING RECORD

FORMATION PLUGGING RECORD

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Corporation Division State Corporation Commission 800 Bitting Building Wichita, Kansas

Strike out upper line when reporting plugging of formations.

Stafford County, Sec. 26, Twp. 24, Rge. 14 (X) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NE 1/4 NE 1/4 NE 1/4

Lease Owner Great Lakes Carbon Corporation

Lease Name L. E. Teetzal Well No. 1

Office Address 501 Petroleum Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12/10/52 19.

Application for plugging filed 12/11/52 19.

Application for plugging approved 12/11/52 19.

Plugging commenced 12/11/52 19.

Plugging completed 12/11/52 19.

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Section plat grid with 'NORTH' label and an asterisk in the top right cell.

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas

Producing formation None Depth to top Bottom Total Depth of Well 3978 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: 13-3/8, 280, None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy rotary mud 3978 to 280'
13-3/8" Halliburton plug 280'
1 sack of hulls on top of plug
20 sacks cement 280 to 220'
Heavy mud 220 to 40'
13-3/8" Halliburton plug 40'
1 sack of hulls on top of plug
15 sacks cement 40 to 6' cellar.

RECEIVED 12-17-52 STATE CORPORATION COMMISSION DEC 17 1952 CONSERVATION DIVISION Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Great Lakes Carbon Corporation Address 501 Petroleum Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. I. D. H. Sholtus (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) I. D. H. Sholtus Dist. Prod. Supt.

501 Petroleum Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 16th day of December, 1952.

My commission expires January 22, 1955

Jack G. Sheakston Notary Public

PLUGGING FILE SEC 26 T 24 R 14 B BOOK PAGE 16 LINE 3

HONAKER DRILLING COMPANY  
2008 LAKIN  
GREAT BEND, KANSAS

DRILLERS LOG

COMPANY: Great Lakes Carbon Corporation  
FARM: Teetzel #1

Sec: 26-24S-14W  
Loc: NE NE NE  
Stafford County, Kansas

Total Depth: 3978'  
Comm: 11-23-52 Comp: 12-11-52  
Contractor: Honaker Drilling Company

Casing: 13 3/8" 280'

Production: D & A

0	160	Sand and Blue Shale	
160	190	Blue Shale	
190	280	Red Bed	Cemented 13 3/8 Casing
280	835	Red Bed and Shale	at 280 ft. with 300 sacks
835	855	Anhydrite	cement.
855	1200	Shale and Shells	
1200	1750	Shale and Lime	
1750	1835	Lime and Shale Streaks	
1835	1905	Lime and Shale	
1905	2055	Lime	
2055	2265	Shale and Lime	
2265	2335	Lime and Shale	
2335	2610	Shale and Lime	
2610	3410	Lime and Shale	
3410	3552	Lime	
3552	3660	Lime and Shale	
3660	3740	Lime	
3740	3762	Lime and Shale	
3762	3978	Lime	
3978	T.D.		

RECEIVED  
STATE COMMISSION  
DEC 20 1952  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is the true and correct copy of the above log, to the best of my knowledge.

*Greg Honaker*

Subscribed and sworn to before me this 18 day of Dec 1952

*Samuel D. Chesler*  
Notary Public

My Commission Expires 6-25-55

PLUGGING  
WELL SEC 26-24S-14W  
BOOK PAGE 66 LINE 3