

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County, Sec. 26 Twp. 24S Rge. 14 (W)

Location as "NE/CNW/SW" or footage from lines SW SW NW

Lease Owner D.R. Lauck Oil Company, Inc.

Lease Name Youse Well No. 1

Office Address 301 South Broadway Wichita Kans

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed November 30 19 55

Application for plugging filed " " 19 55

Application for plugging approved " " 19 55

Plugging commenced " " 19 55

Plugging completed " " 19 55

Reason for abandonment of well or producing formation

dry hole

If a producing well is abandoned, date of last production -- 19 55

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage

Producing formation -- Depth to top -- Bottom -- Total Depth of Well 4270 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	159	8 5/8	159'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

hole filled with heavy mud;  
85 sacks of cement pumped in on top of plug;

RECEIVED  
STATE CORPORATION COMMISSION

DEC 10 1955 12-10-55

CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing Co.

Address Great Bend Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.

John H. Knightley (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Knightley  
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 9th day of December, 19 55

My commission expires Sept. 14, 1959

Elizabeth Kay  
Notary Public

PLUGGING  
FILED SEC. 26 T. 24 S. R. 14 W.  
PAGE 21 LINE 6

D. R. Lauck Oil Company, Inc

Youse #1

SW SW NW Sec. 26-24S-14W  
Stafford County KansasCommenced: November 16, 1955  
Completed: November 30, 1955

Casing Record: 159' 8 5/8" cemented with 160 sacks

Elevation: GR 1938; DF 1940; KB 1942;

Drillers LogTops

Sand	120	Anhydrite	837	pl	1105
Shale & shells	159	Heebner	3469	-	1527
blue shale	180	Brown Lime	3604	-	1662
red bed & shells	335	Lansing	3636	-	1694
sand	375	Mississippian	3994	-	2052
red bed	515	Viola	4069	-	2127
red bed, shale & shells	837	Simpson shale	4182	-	2240
Anhydrite	870	Arbuckle	4231	-	2289
shale & shells	940	Rotary Total Depth	4270	-	2328
red bed, shale & shells	1185				
salt & shale	1275				
red bed & shale	1470	DST #1	3659-3675	open 30 min;	
shale & shells	1720			weak blow 7 min; recovered 50'	
shale & lime	1950			mud; BHP 840# in 20 min. and	
lime	2010			still building	
lime & shale	3604				
lime	4041				
lime & chert	4075				
lime	4135				
chert & Lime	4155				
lime	4185				
lime & shale	4255				
lime	4270				
Rotary TD	4270				

D &amp; A

RECEIVED  
STATE CORPORATION COMMISSION

DEC 10 1955

