

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-22,467-0000

LEASE NAME Koelsch

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #1-27

2310 Ft. from S Section Line

2970 Ft. from E Section Line

LEASE OPERATOR Petro Locators, Inc.

ADDRESS PO Box 77, Pratt, KS 67124

PHONE#( 316 672-3040 OPERATORS LICENSE NO. 9740

Character of Well \_\_\_\_\_

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

SEC. 27 TWP. 24 RGE. 14 ~~X~~ (W)

COUNTY Stafford

Date Well Completed 10-11-87

Plugging Commenced 10-11-87

Plugging Completed 10-11-87

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dist #1 - Dodge City - Dick Kapp

Is ACO-1 filed? operator will be by \_\_\_\_\_  
If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 4270'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Plug #1 set at 900' with 40 sacks cement through drill pipe  
Plug #2 set at 290' with 40 sacks cement through drill pipe  
Plug #3 set at 40' with 10 sacks cement; 15 sacks in rat hole; filled water well

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address PO Box 823, Great Bend, KS 67530

STATE OF KANSAS COUNTY OF BARTON, ss.


Leonard Williamson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) PO Box 823, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 14 day of October, 19 87

Dorothy M. Clark  
Notary Public  
STATE CORPORATION COMMISSION



OCT 19 1987  
CONSERVATION DIVISION Form CP-4  
Wichita, Kan. Revised 07-86

DRILLERS WELL LOG

DATE COMMENCED: October 3, 1987  
DATE COMPLETED: October 11, 1987

Petro Locators, Inc.  
Koelsch #1-27  
NE NE SW  
Sec. 27-T24s-R14W  
Stafford County, KS

ELEVATION: 1978' K.B.

0 - 875'	Surface Soil, Shale, Red Bed
875 - 901'	Anhydrite
901 - 3097'	Shale
3097 - 3512'	Lime & Shale
3512 - 3517'	Shale
3517 - 3677'	Lime & Shale
3677 - 3950'	Lime
3950 - 4202'	Chert, Lime
4202 - 4215'	Shale
4215 - 4250'	Sand, Lime
4250 - 4270'	Dolomite

FORMATION DATA

Anhydrite	875 - 901'
Howard	3097'
Topeka	3187'
Heebner	3512'
Toronto	3538'
Douglas	3552'
Brown Lime	3646'
Kansas City	3677'
Base K.C.	3950'
Mississippi	4051'
Viola	4126'
Simpson Shale	4202'
Simpson Sand	4215'
Arbuckle	4250'
RTD	4270'

Surface Pipe: Set new 20# 8-5/8" pipe at 259' with 160 sacks 60/40 pozmix, 2% gel, 3% c.c.


A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

LEONARD WILLIAMSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

*Leonard Williamson*  
Leonard Williamson

SUBSCRIBED AND SWORN to before me this 16th day of October, 1987.



*Dorothy M. Hague*  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

OCT 19 1987

CONSERVATION DIVISION  
Wichita, Kansas