

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
OCT 4 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name H.C. Bennett 15-079-19039-0000

Complete Address: 1212 Union National Building. Wichita, Kansas

Lease Name Hurty Well No. # 1

Location SW NW NW Sec. 18 Twp. 23 Rge. 3 (E) (W)

County Harvey Total Depth 3381'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Flint Engin. & Const. Co.

Address: El Dorado, Kansas License No. 547

Operation Completed: Hour 4 PM Day 2 Month 10 Year 67

The Above well was plugged as follows:

8 5/8"-496'-Circulated w/cement. 5 1/2"-3315'-Cemented. Sand hole to 3310'.
5 Sax. cement 3310' to 3260'. Mud 3260' to 200'. Bridge 200' to 190'.
25 Sax. cement 190' to 115'. Mud 115' to 40'. Bridge 40' to 30'.
10 Sax. cement 30' to 0. Pulled 2300'-5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Hugh Scott
Well Plugging Supervisor

DATE 10-4-67

INV. NO. 7068-E