

KANSAS

Al STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-079-19057-0600

RECEIVED
STATE CORPORATION COMMISSION
SEP 11 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Bennett & Gould

Complete Address: 1212 Union National Building. Wichita, Kansas 67202

Lease Name Short Well No. # 2

Location C W/2 NE NW Sec. 18 Twp. 23 Rge. 3 (E) (W)

County Harvey Total Depth 3373'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Art Lamb Casing Pulling Company

Address: Hutchinson, Kansas License No. # 440

Operation Completed: Hour 1 1/2 AM Day 9 Month 9 Year 68

The Above well was plugged as follows:

8 5/8"-248'-Circulated w/cement. 5 1/2"-3324'-Cemented. Sand hole to 3300'.
5 Sx.cement 3300' to 3250'. Mud 3250' to 240'. Bridge 240' to 230'.
25 Sx.cement 230' to 155'. Mud 155' to 40'. Bridge 40' to 30'.
10 Sx.cement 30' to 0. Pulled 3015'-5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9/11/68
INV. NO. 8030-E

Signed: *Hugh Scott*
Well Plugging Supervisor