

KANSAS

Form CP-3  
Rev. 6-26-62

R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 13 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Bennett & Gould 15.079-19056-0000

Complete Address: 1212 Union National Building, Wichita, Kansas 67202

Lease Name Short Well No. # 1

Location SW NE NW Sec. 18 Twp. 23S Rge. 3 (E) (W)

County Harvey Total Depth 3373'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Art Lamb Casing Pulling Company

Address: Hutchinson, Kansas License No. # 440

Operation Completed: Hour 10 AM Day 11 Month 9 Year 68

The Above well was plugged as follows:

8 5/8"-165'-Circulated w/cement. 5 1/2"-3285'-Cemented. Sand hole to 3275'.

5 Sax.cement 3275' to 3225'. Mud 3225' to 175'. Bridge 175' to 165'.

25 Sax.cement 165' to 90'. Mud 90' to 40'. Bridge 40' to 30'.

10 Sax.cement 30' to 0. Pulled 2600'-5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 9-13-68

INV. NO. 8645-E