

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Home Stake Production Company 15-079-19129-0000

Complete Address: Box 68 Burrton, Kansas 67020

Lease Name Brilhart "B" Well No. # 0-15

Location W/2 NW Sec. 31 Twp. 23 Rge. 3 (B)V (W)

County Harvey Total Depth 3365'

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Co.

Address: Chase, Kansas License No. # 624

Operation Completed: Hour 11 AM Day 24 Month 6 Year 68

The Above well was plugged as follows:

10 3/4"-507' -Circulated w/cement. 5 1/2"-3330' -Cemented. Sand hole to 3320'.

5 SAX.cement 3320' to 3270'. Mud 3270' to 310'. Bridge 310' to 300'.

35 SAX.cement 300' to 225'. Mud 225' to 40'. Bridge 40' to 30'.

15 SAX.cement 30' to 0. Pulled 2470'-5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: High Scott
Well Plugging Supervisor

DATE 6-26-68

INV. NO. 8297-E