

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUL 8 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Home Stake Production Company 15-079-19128-0000

Complete Address: Box 68 Burrton, Kansas 67020

Lease Name Brilhart Well No. # 1

Location NE NW NW Sec. 31 Twp. 23 Rge. 3 (E)/(W)

County Harvey Total Depth 3362'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Chase, Kansas License No. # 624

Operation Completed: Hour 3 PM Day 5 Month 7 Year 68

The Above well was plugged as follows:

10"-280'-Circulated w/cement. 7"-3269'-Cemented. Sand hole to 3260'.
7 Sax.cement 3260' to 3200'. Mud 3200' to 280'. Bridge 280' to 270'.
35 Sax.cement 270' to 200'. Mud 200' to 40'. Bridge 40' to 30'.
15 Sax.cement 30' to 0. Pulled 2335'-7"-pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Hugh Scott
Well Plugging Supervisor

DATE 7-8-68

INV. NO. 8342-E