

RP

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Home Stake Production Co. 15-079-00423-0000

Complete Address: Box 68 Burrton, Kansas 67020

Lease Name Schrag B Well No. # 1

Location NW NE NW Sec. 31 Twp. 23 Rge. 3 (E) (W)

County Harvey Total Depth 3368'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co. Inc.

Address: Chase, Kansas License No. # 436

Operation Completed: Hour 3 PM Day 5 Month 6 Year 68

The Above well was plugged as follows:

10"-264'-Circulated w/cement. 7"-3264'-Cemented. 5 1/2"-linner-500' Cemented.
Sand hole to 3250'. 6 Sax.cement 3250' to 3200'. Mud 3200' to 280'.
Bridge 280' to 270'. 30 Sax.cement 270' to 200'. Mud 200' to 40'.
Bridge 40' to 30'. 15 Sax.cement 30' to 0. Pulled 2384'-7"-pipe.
Pulled 500' - 5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6-7-68

INV. NO. 8209-E

Signed: *Hugh [Signature]*
Well Plugging Supervisor