

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 14 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name R.L. Evans Estate 15-079-20622-0600

Complete Address 3803 Panorama Road. Hutchinson, Kansas 67501

Lease Name Base Well No. # 1

Location NW NW SW Sec. 31 Twp. 23 Rge. (E) 3(W)

County Harvey Total Depth 3340'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Art Lamb Casing Pulling

Address Hutchinson, Kansas License No. 440

Operation Completed: Hour 5 PM Day 12 Month 3 Year 74

The above well was plugged as follows:

10"-277'-Circulated w/cement. 5 1/2"-3332'-Cemented. Plug back to 3324'.

Top perf. 3306'. Sand to 3275'. 5 Sax. Cement at 3275'.

Mud to 300'. Bridge 300' to 290'. 35 Sax. Cement at 290'.

Mud to 40'. Bridge 40' to 30'. 15 Sax. Cement 30' to 0.

Pulled 2700'-5 1/2"-Pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 3/18/74

INV. NO. 6474-E