

SP

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 14 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Home Stake Production Comoany <sup>079</sup> 15-077-19137-0000

Complete Address: Box 68 Burrton, Kansas 67020

Lease Name Schrag B Well No. 0-10

Location NE NE NW Sec. 31 Twp. 23 Rge. 3 (E) (W)

County Harvey Total Depth 3364'

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Chase, Kansas License No. 436

Operation Completed: Hour 4 PM Day 12 Month 6 Year 68

The Above well was plugged as follows:

8 5/8"-495'-Circulated w/cement. 5 1/2"-3333'-Cemented. Sand hole to 3320'.

5 Sax.cement 3320' to 3270'. Mud 3270' to 310'. Bridge 310' to 300'.

25 Sax.cement 300' to 225'. Mud 225' to 40'. Bridge 40' to 30'.

10 Sax.cement 30' to 0. Pulled 2462'-5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 6-14-68

INV. NO. 8244-E