

R

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-155-02741-0000 (of this well)

Operator's Full Name Kantor Oil Company  
Complete Address 2101 Phillower Bldg., Tulsa, Oklahoma 74103  
Lease Name Joseph Goering Well No. 1  
Location NW NW NE Sec. 1 Twp. 23 Rge. 4 (E) (W) X  
County Renov Total Depth 3353'  
Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling  
Address Box 176, Chase, Kansas License No. 683

Operation Completed: Hour 3:30 PM Day 24 Month October Year 1979

The above well was plugged as follows: 12 1/2" - 320' - 250 sacks 8 1/4" - 3234' - 250 sacks  
4 1/2" - 2140' - on packer.  
4 1/2" casing jumped out of slips and went down hole - Top at 864'.  
Rashed plug to 864' Filled hole with sand to 830' and cemented  
hole with 8 sacks cement. Bailed hole to 320'. Set rock bridge  
From 320' to 300' and cemented to base of collar with 10 yards  
ready-mix concrete.  
709' of 8 1/4" casing recovered.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 29 1979  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 10-30-79  
INV. NO. 0768-W

Signed: Arthur J. [Signature]  
Well Plugging Supervisor