

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-10490-00-00
Spot: CNENENW Sec/Twnshp/Rge: 10-24S-15W
330 feet from N Section Line, 2310 feet from W Section Line
Lease/Unit Name: SUITER B Well Number: 1
County: STAFFORD Total Vertical Depth: 4105 feet

Operator License No.: 5010
Operator Name: KNIGHTON OIL COMPANY, INC.
Address: 710 PETROLEUM BUILDING
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 242 WITH 185 SX CMT
Production: Size 5.5 feet: 4104 WITH 75 SX CMT
Liner: Size _____ feet: 133.41

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/06/2000 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: CARL GILPIN Company: KNIGHTON OIL Phone: (785) 623-4081

Proposed Plugging Method: SAND TO 2550' & 5 SX CMT ON TOP. PERFORATE AT 950' CIRCULATE TO SURFACE.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/06/2000 9:55 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:
PERFS AT 2608-4049'. CIBP SET @ 2550'. PERFORATED 5 1/2" AT 950'. PUMPED 330 SX CMT DOWN 5 1/2" CASING CIRCULATING CMT TO SURFACE UP 8 5/8" X 5 1/2" ANNULAS.

RECEIVED
STATE CORPORATION COMMISSION
12-11-00
DEC 11 2000

Remarks: USED 65/35 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.
Plugged through: CSG

CONSERVATION DIVISION
Wichita, Kansas

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

INVOICED
DATE 12/12/00
INV. NO. 200106116

DEC 08 2000

Form CL 200

NO