

2-9

1 120374

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-01,929-0001

NW SE NE, SEC. 4, T 24 S, R 15 W/E  
3630 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Lease Name Lucas Well # 1

Operator: AP 1990  
Name: Shell Petroleum

County Stafford 135.01

Address: 412 Division East Douglas, Suite One  
Wichita, Kansas

Well Total Depth 4154 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 255

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 9 Month: 2 Year: 1990

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4152' PBD 4098' Perfs at 4019-89'

1st plug pump in 4 1/2" casing with 100 lbs. hulls and 20 sx cement,

2nd plug pump in 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, and 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:30 p.m. Day: 9 Month: 2 Year: 1990

ACTUAL PLUGGING REPORT 1st plug pumped into 4 1/2" casing with 100 lbs. hulls and 20 sx

cement, pushed plug to 3500', shut in pressure at 1150 psi.

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls and 125 sx cement.

Pumping pressure 0-700 psi and shut in 150 psi.

FEB 14 1990

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2040' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Duane Rankin (TECHNICIAN)

DATE 2-16-90

INV. NO. 27475